

**De Portola Road Drainage Improvements Project
Shiraz Way to 650-Foot Northerly
Community of Rancho California
Project No. D0-0099**

PROPOSAL

ITEM No.	ITEM CODE	ITEM	UNIT	ESTIMATED QUANTITY	ITEM PRICE (IN FIGURES)	TOTAL (IN FIGURES)
BASE BID SCHEDULE - De Portola Road Drainage Improvements						
1	066100	DUST ABATEMENT	LS	1		
2	100100	DEVELOP WATER SUPPLY	LS	1		
3	120100	TRAFFIC CONTROL SYSTEM	LS	1		
4	130200	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	1		
5	170103	CLEARING AND GRUBBING	LS	1		
6	015602	FUNDING AWARENESS SIGN	EA	1		
7	190101	ROADWAY EXCAVATION	CY	278		
8	190151 F	CHANNEL EXCAVATION	CY	1,200		
9	032001	RELOCATE BUSINESS SIGN	EA	1		
10	032002	EARTHEN SWALE	LF	511		
11	202028	RELOCATE IRRIGATION CONTROLLER	EA	6		
12	260203	CLASS 2 AGGREGATE BASE	CY	210		
13	013903	PLACE ASPHALT CONCRETE DIKE (CRS 212) (6")	LF	563		
14	390132	HOT MIX ASPHALT (TYPE A)	TON	181		
15	475000 F	RETAINING WALL -TYPE 1A	SQFT	7,674		
16	510050	STRUCTURAL CONCRETE [CHANNEL TRANS STRUCTURE]	SQYD	276		
17	510050	STRUCTURAL CONCRETE [WIER STRUCTURE]	SQYD	425		
18	510050	STRUCTURAL CONCRETE [CHANNEL JUNCTION STRUCT]	SQYD	326		
19	600029	REMOVE ASPHALT CONCRETE SURFACING	SQFT	487		
20	037001	36"X36"X48" PRECAST DROP INLET	EA	1		
21	723190	CONCRETED-ROCK SLOPE PROTECTION (20 lb, Class I, METHOD B)	CY	42		
22	017302	MINOR CONCRETE (CROSS-GUTTER/SPANDRAL) (CRS 209)	SQFT	1,545		
23	839521	CABLE RAILING	LF	520		
24	810120	REMOVE PAVEMENT MARKER	SQ FT	198		
25	820112	MARKER (CULVERT)	EA	4		

PROPOSAL

ITEM No.	ITEM CODE	ITEM	UNIT	ESTIMATED QUANTITY	ITEM PRICE (IN FIGURES)	TOTAL (IN FIGURES)
BASE BID SCHEDULE - De Portola Road Drainage Improvements (continued)						
26	820410	SALVAGE ROADSIDE SIGN	EA	8		
27	820840	ROADSIDE SIGN - ONE POST	EA	5		
28	840519	THERMOPLASTIC CROSSWALK AND PAVEMENT MARKING	SQFT	320		
29	840656	PAINT TRAFFIC STRIPE (2-COAT)	LF	570		
30	870700	FLASHING BEACON SYSTEM	LS	1		
31	010602	MISCELLANEOUS WORK (AS DIRECTED)	FA	1	192,000.00	192,000.00

PROJECT

TOTAL: _____ \$ _____

ITEMS 1 - 31

"WORDS"