

**Skyview Road Pedestrian Bridge
Over French Valley Channel
Community of French Valley
Project No. C9-0015**

PROPOSAL

ITEM No.	ITEM CODE	ITEM	UNIT	ESTIMATED QUANTITY	ITEM PRICE (IN FIGURES)	TOTAL (IN FIGURES)
BASE BID SCHEDULE - Skyview Pedestrian Road Bridge over French Valley Channel						
1	999990	MOBILIZATION [INCLUDES DEMOBILIZATION AND FINAL CLEANUP]	LS	1		
2	019902	COURSE OF CONSTRUCTION INSURANCE	LS	1		
3	066105	RESIDENT ENGINEER OFFICE	LS	1		
4	066100	DUST ABATEMENT	LS	1		
5	131201	TEMPORARY CREEK DIVERSION SYSTEM	LS	1		
6	015602	FUNDING AWARENESS SIGN	EA	2		
7	120100	TRAFFIC CONTROL SYSTEM	LS	1		
8	130301	STORMWATER POLLUTION PREVENTION PLAN	LS	1		
9	160110	TEMPORARY HIGH-VISIBILITY FENCE	LF	974		
10	170103	CLEARING AND GRUBBING	LS	1		
11	190140	TRENCH EXCAVATION [FOR RCP AND RCB]	CY	662		
12	193001	STRUCTURE BACKFILL [TRENCH BACKFILL FOR RCP AND RCB]	CY	411		
13	260200	AGGREGATE BASE [3/4" CRUSHED ROCK, TRENCH BEDDING FILTER MATERIAL FOR RCP]	CY	9		
14	031902	TRENCH CONTROLLED LOW-STRENGTH MATERIAL FOR RCP	CY	34		
15	035101 F	ARCHITECTURAL TREATMENT (COLORED STAMPED CONCRETE, AGGREGATE EXPOSED CONCRETE, PREPARED AND STAIN CONCRETE)	SQFT	6,400		
16	038301 F	CONCRETE BARRIER	LF	821		
17	192003 F	STRUCTURE EXCAVATION (BRIDGE)	CY	112		
18	192020 F	STRUCTURE EXCAVATION (TYPE D)	CY	20		
19	193003 F	STRUCTURE BACKFILL (BRIDGE)	CY	70		
20	490603	24" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	271		
21	490608	54" CAST-IN-DRILLED-HOLE CONCRETE PILING	LF	259		
22	500001	PRESTRESSING CAST-IN-PLACE CONCRETE	LS	1		
23	510051 F	STRUCTURAL CONCRETE. BRIDGE FOOTING	CY	4		
24	510053 F	STRUCTURAL CONCRETE. BRIDGE	CY	342		
25	510054 F	STRUCTURAL CONCRETE, BRIDGE (POLYMER FIBER)	CY	200		
26	510086 F	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)	CY	20		
27	519092	JOINT SEAL ASSEMBLY (MR 2 1/2")	LF	34		
28	520102 F	BAR REINFORCING STEEL (BRIDGE)	LB	221,724		
29	750501 F	MISCELLANEOUS METAL (BRIDGE)	LB	780		
30	780460 F	ANTI-GRAFFITI COATING	SQFT	10,142		

PROPOSAL

ITEM No.	ITEM CODE	ITEM	UNIT	ESTIMATED QUANTITY	ITEM PRICE (IN FIGURES)	TOTAL (IN FIGURES)
BASE BID SCHEDULE - Skyview Pedestrian Road Bridge over French Valley Channel (Continued)						
31	833090 F	TUBULAR HAND RAILING (MODIFIED)	LF	821		
32	202004	IRON SULFATE	LB	185		
33	202006	SOIL AMENDMENT	CY	30		
34	202038	PACKET FERTILIZER	EA	1,998		
35	204011	PLANT (GROUP K)	EA	9		
36	204035	PLANT (GROUP A)	EA	512		
37	204036	PLANT (GROUP B)	EA	447		
38	204038	PLANT (GROUP U)	EA	3		
39	204096	MAINTAIN EXISTING PLANTED AREAS	LS	1		
40	204099	PLANT ESTABLISHMENT WORK [12 MONTHS]	LS	1		
41	205034	DECOMPOSED GRANITE	SF	2,329		
42	205035	WOOD MULCH	CY	67		
43	205062	ROOT BARRIER	LF	24		
44	206560	CONTROL AND NEUTRAL CONDUCTORS	LS	1		
45	206562	1" REMOTE CONTROL VALVE	EA	1		
46	208445	TREE WELL SPRINKLER ASSEMBLY	EA	18		
47	208594 F	3/4" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	1,525		
48	208595 F	1" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	31		
49	208596 F	1 1/4" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	35		
50	208640	PRESSURE REGULATING VALVE	EA	38		
51	208649	QUICK COUPLING VALVE	EA	3		
52	208670	CHECK VALVE	EA	16		
53	208683	BALL VALVE	EA	2		
54	208690 F	PVC PIPE CONDUIT (SLEEVE)	LF	40		
55	210110	IMPORTED TOPSOIL	CY	67		
56	038001	DOUBLE TUBULAR STEEL GATE	LS	1		
57	038002	TUBULAR STEEL FENCE	LF	119		
58	032001	BASKET FILTER	EA	8		
59	032002	DRIP EMITTER	EA	941		
60	032003	FLUSH VALVE	EA	7		
61	208220 F	1/2" DRIP IRRIGATION TUBING	LF	3,000		
62	208423	1" BACKFLOW PREVENTER ASSEMBLY	EA	1		
63	208442	FLOW SENSOR	EA	1		
64	208450	DRIP VALVE ASSEMBLY	EA	4		

PROPOSAL

ITEM No.	ITEM CODE	ITEM	UNIT	ESTIMATED QUANTITY	ITEM PRICE (IN FIGURES)	TOTAL (IN FIGURES)
BASE BID SCHEDULE - Skyview Pedestrian Road Bridge over French Valley Channel (Continued)						
65	208597 F	1 1/2" PLASTIC PIPE (SCHEDULE 40) (SUPPLY LINE)	LF	154		
66	032006	MASTER VALVE	EA	1		
67	032007	8-STATION CONTROLLER (PEDESTAL MOUNTED)	EA	1		
68	995100	WATER METER CHARGES	LS	1		
69	032004	RECONSTRUCT IRRIGATION SYSTEM	LS	1		
70	032005	REPLACE LANDSCAPING IN KIND	LS	1		
71	260203	CLASS 2 AGGREGATE BASE	CY	91		
72	390132	HOT MIX ASPHALT (TYPE A)	TON	63		
73	398001	REMOVE ASPHALT CONCRETE PAVEMENT (SQFT)	SQFT	8,779		
74	017112	CONSTRUCT JUNCTION STRUCTURE NO. 1 (PIPE TO BOX)	EA	1		
75	017113	CONSTRUCT TRANSITION STRUCTURE NO 1. (PIPE TO BOX)	EA	1		
76	017109	CONSTRUCT MANHOLE NO. 3 (UNIT PRICE INCLUDES REBAR)	EA	2		
77	710180	RECONSTRUCT DRAINAGE FACILITY [EXISTING INLET STRUCTURE IN BASIN FOR CULVERT "7"]	EA	1		
78	710180	RECONSTRUCT DRAINAGE FACILITY [EXISTING INLET STRUCTURE IN BASIN FOR LINE "G"]	EA	1		
79	510058 F	STRUCTURAL CONCRETE, WALL	CY	7		
80	510090 F	STRUCTURAL CONCRETE, BOX CULVERT [8'W BY 3'H RCB INCLUDING REBAR]	CY	50		
81	510090 F	STRUCTURAL CONCRETE, BOX CULVERT [4'W BY 2'H RCB INCLUDING REBAR]	CY	19		
82	510050 F	STRUCTURAL CONCRETE [BOX CULVERT WINGWALLS PER CALTRANS STD PLAN D84(TYPE A)]	CY	68		
83	510502	MINOR CONCRETE (MINOR STRUCTURE) [CATCH BASIN, CONCRETE COLLAR, UNDER SIDEWALK DRAIN]	CY	6		
84	650411	18" REINFORCED CONCRETE PIPE (CLASS IV)	LF	133		
85	650014	18" REINFORCED CONCRETE PIPE	LF	145		
86	680285	4" PLASTIC PIPE UNDERDRAIN	LF	326		
87	480600	TEMPORARY SHORING [TRENCH SAFETY SYSTEM]	LS	1		
88	723050	ROCK SLOPE PROTECTION (1/4 T, CLASS V, METHOD B) [RIPRAP, T=2.7']	CY	33		
89	682042 F	CLASS 2 PERMEABLE MATERIAL (BLANKET) [9" FILTER MATERIAL, TYPE B]	CY	9		
90	039601	FILTER FABRIC	SQYD	1,444		
91	721810	SLOPE PAVING (CONCRETE) [6" THICK CONCRETE SLOPE LINING INCLUDING REBAR]	CY	15		
92	723050	ROCK SLOPE PROTECTION (1/4 T, CLASS V, METHOD B)	CY	220		
93	731509	MINOR CONCRETE (CONCRETE MOW STRIP)	CY	4		
94	731510	MINOR CONCRETE (CURB, GUTTER, SIDEWALK,AND DRIVEWAY)	CY	43		
95	731519	MINOR CONCRETE (STAMPED CONCRETE)	SQFT	3,448		
96	780254	ADJUST ACCESS BOX FRAME AND COVER (UTILITY)	EA	4		
97	037501	REMOVEABLE STEEL PIPE BOLLARDS	EA	6		
98	038003	CONSTRUCT CHAIN LINK FENCE	LF	51		

PROPOSAL

ITEM No.	ITEM CODE	ITEM	UNIT	ESTIMATED QUANTITY	ITEM PRICE (IN FIGURES)	TOTAL (IN FIGURES)
BASE BID SCHEDULE - Skyview Pedestrian Road Bridge over French Valley Channel (Continued)						
99	038004	CONSTRUCT STEEL GATE/FENCE	LF	26		
100	038302	INSTALL GUARD RAIL	LF	8		
101	510502	MINOR CONCRETE (MINOR STRUCTURE) [CONCRETE COLLAR]	EA	1		
102	510502	MINOR CONCRETE (MINOR STRUCTURE) [2' CUT-OFF WALL INCLUDING REBAR]	LF	76		
103	680283	3" PLASTIC PIPE UNDERDRAIN [PERFORATED, PVC SCH 40, INCLUDES ALL FITTINGS AND BENDS]	LF	1,306		
104	680281	2" PLASTIC PIPE UNDERDRAIN [PVC SCH 40, INCLUDES ALL FITTINGS AND BENDS]	LF	29		
105	681502	PERMEABLE MATERIAL (BLANKET) [3/4" GRAVEL, BASIN BOTTOM]	CY	350		
106	031901	REMOVE AND DISPOSE 24" OF EXISTING SOIL IN THE BASIN FLOOR AREA AND REPLACE WITH CLEAN, COMPACTED SOIL (RAW QUANTITY)	CY	929		
107	740500	DRAINAGE PUMPING EQUIPMENT [INSTALL LIFT STATION (SUMP PUMP)]	EA	1		
108	820840	ROADSIDE SIGN - ONE POST	EA	2		
109	820850	ROADSIDE SIGN - TWO POSTS	EA	2		
110	870200	LIGHTING SYSTEM	LS	1		
111	802601	14' CHAIN LINK DOUBLE DRIVE GATE (CL-6)	EA	1		
112	010602	MISCELLANEOUS WORK (AS DIRECTED)	FA	1	200,000.00	200,000.00

BASE BID SCH.

SUB-TOTAL: _____ \$ _____
ITEMS 1 - 112 "WORDS"

ALTERNATIVE BID SCHEDULE 1 - Eastern Municipal Water District, Water Line Relocation

113	037701	RELOCATE APPROXIMATELY 75 LF OF 18" CML&C STEEL WATERLINE AND APPURTENANCES	LS	1		
-----	--------	---	----	---	--	--

ALT. BID SCH. 1

SUB-TOTAL: _____ \$ _____
ITEM 113 "WORDS"

BASE BID SCH. 1 + ALT. BID SCH. 1

PROJECT TOTAL: _____ \$ _____
ITEMS 1 - 113 "WORDS"