

**Clark Street  
Resurfacing and Sidewalk Improvements Project  
Martin Street to Nandina Avenue  
Community of Mead Valley  
Project No. C9-0026, D3-0111**

**PROPOSAL**

ITEM No.	ITEM CODE	ITEM	Like Bid Item*	UNIT	ESTIMATED QUANTITY	ITEM PRICE (IN FIGURES)	TOTAL (IN FIGURES)
<b>BASE BID SCHEDULE 1 - Clark Street, Martin Street to Oleander Avenue, D3-0111</b>							
1	066100	DUST ABATEMENT	-----	LS	1		
2	100100	DEVELOP WATER SUPPLY	-----	LS	1		
3	120100	TRAFFIC CONTROL SYSTEM	-----	LS	1		
4	130300	PREPARE STORM WATER POLLUTION PREVENTION PLAN	-----	LS	1		
5	170103	CLEARING AND GRUBBING	-----	LS	1		
6	038001	WOOD FENCE	-----	LF	12		
7	190101 F	ROADWAY EXCAVATION	-----	CY	7,810		
8	198010 F	IMPORTED BORROW	-----	CY	1,090		
9	260203	CLASS 2 AGGREGATE BASE	-----	CY	5,170		
10	013903	PLACE ASPHALT CONCRETE DIKE (CRS 212) (6")	-----	LF	80		
11	013908	ASPHALT CONCRETE DRIVEWAY	Like 1	SQFT	13,044		
12	390132	HOT MIX ASPHALT (TYPE A)	Like 2	TON	6,416		
13	017114	TRANSITION STRUCTURE (RCFC&WCDS TS 303)	-----	EA	1		
14	035101	REINFORCED CONCRETE RETAINING WALL (TYPE 6)	-----	SQFT	228		
15	035102	CONCRETE BLOCK SLOUGH WALL (SPPWC STD PLAN 622-4)	-----	LF	37		
16	035103	HEADWALL AND WING WALL (CALTRANS D90)	-----	CY	3		
17	650014	18" REINFORCED CONCRETE PIPE	-----	LF	49		
18	650018	24" REINFORCED CONCRETE PIPE	-----	LF	128		
19	035104	CURB INLET CATCH BASIN WITH HEADWALL MODIFIED (CRS 300 & CALTRANS D89A)	-----	EA	3		
20	017003	CATCH BASIN (CURB INLET) (CRS 300)	-----	EA	2		
21	705206	24" CONCRETE FLARED END SECTION	-----	EA	1		
22	723080	ROCK SLOPE PROTECTION (60 lb, Class II, METHOD B)	-----	CY	23		
23	729011	ROCK SLOPE PROTECTION FABRIC (CLASS 8)	-----	SQYD	240		
24	017304	MINOR CONCRETE (CURB AND GUTTER) (CRS 200)	-----	LF	5,141		
25	017310	MINOR CONCRETE (DRIVEWAY APPROACH) (CRS 207)	-----	SQFT	3,035		
26	017316	MINOR CONCRETE (CURB RAMP) (CRS 403 - CASE B)	-----	EA	23		
27	017317	MINOR CONCRETE (CROSS-GUTTER AND SPANDREL) [CRS 209]	Like 3	SQFT	10,111		

**PROPOSAL**

ITEM No.	ITEM CODE	ITEM	Like Bid Item*	UNIT	ESTIMATED QUANTITY	ITEM PRICE (IN FIGURES)	TOTAL (IN FIGURES)
<b>BASE BID SCHEDULE 1 - Clark Street, Martin Street to Oleander Avenue, D3-0111 (continued)</b>							
28	037301	MINOR CONCRETE (ALLEY APRON) (CRS 500)	-----	CY	7		
29	731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION) [BUS PAD]	-----	CY	86		
30	731516	MINOR CONCRETE (DRIVEWAY)	-----	CY	4		
31	731521	MINOR CONCRETE (SIDEWALK) [CRS 401]	-----	SQFT	23,490		
32	780433	PAINT CURB (2-COAT) [RED]	-----	LF	50		
33	782120	RELOCATE MAILBOX	Like 4	EA	13		
34	800360	CHAIN LINK FENCE (TYPE CL-6)	-----	LF	46		
<b>34.A</b>	<b>800103</b>	<b>TEMPORARY FENCE (TYPE CL-6)</b>	<b>-----</b>	<b>LF</b>	<b>101</b>		
<b>34.B</b>	<b>802521</b>	<b>TEMPORARY 6' CHAIN LINK GATE (TYPE CL-6)</b>	<b>-----</b>	<b>EA</b>	<b>4</b>		
35	<b>000001</b>	<b>ITEM DELETED PER ADDENDUM No. 1</b>	-----	---	---	---	---
36	810230 F	PAVEMENT MARKER (RETROREFLECTIVE)	Like 5	EA	422		
37	820590	RELOCATE ROADSIDE SIGN-ONE POST	Like 6	EA	30		
38	833085	METAL HAND RAILING	-----	LF	146		
39	840515 F	THERMOPLASTIC PAVEMENT MARKING	Like 7	SQFT	644		
40	840519 F	THERMOPLASTIC CROSSWALK AND PAVEMENT MARKING	Like 8	SQFT	513		
41	840656 F	PAINT TRAFFIC STRIPE (2-COAT)	Like 9	LF	10,204		
42	015602	FUNDING AWARENESS SIGN	Like 10	EA	1		
43	010602	MISCELLANEOUS WORK (AS DIRECTED)	-----	FA	1	<b>340,000.00</b>	<b>340,000.00</b>

BASE BID SCH. 1

SUB-TOTAL: \_\_\_\_\_ \$ \_\_\_\_\_

ITEMS 1-43 "WORDS"

\* NOTE: See Instructions to Bidders, Section 16 "Like Bid Items", on page A9; corrections will apply if Like Bid items cost discrepancies are submitted. Applicable only to Alternative Bid Schedules 1 and 2. Base Bid Schedule 1 is not included.

**BASE BID SCHEDULE 2 - Clark Street, Oleander Avenue to Nandina Avenue, C9-0026**

44	066100	DUST ABATEMENT	-----	LS	1		
45	100100	DEVELOP WATER SUPPLY	-----	LS	1		
46	120100	TRAFFIC CONTROL SYSTEM	-----	LS	1		
47	130300	PREPARE STORM WATER POLLUTION PREVENTION PLAN	-----	LS	1		
48	170103	CLEARING AND GRUBBING	-----	LS	1		
49	011505	GRINDING ASPHALT CONCRETE IN PLACE	-----	SQYD	9,555		
50	013908	ASPHALT CONCRETE DRIVEWAY	Like 1	SQFT	9,506		
51	390132	HOT MIX ASPHALT (TYPE A)	Like 2	TON	2,810		
52	394075	PLACE HOT MIX ASPHALT DIKE (TYPE D)	-----	LF	426		

**PROPOSAL**

ITEM No.	ITEM CODE	ITEM	Like Bid Item*	UNIT	ESTIMATED QUANTITY	ITEM PRICE (IN FIGURES)	TOTAL (IN FIGURES)
<b>BASE BID SCHEDULE 2 - Clark Street, Oleander Avenue to Nandina Avenue, C9-0026 (continued)</b>							
53	017317	MINOR CONCRETE (CROSS-GUTTER AND SPANDREL) [CRS 209]	Like 3	SQFT	640		
54	782120	RELOCATE MAILBOX	Like 4	EA	1		
55	810230 F	PAVEMENT MARKER (RETROREFLECTIVE)	Like 5	EA	206		
56	820590	RELOCATE ROADSIDE SIGN-ONE POST	Like 6	EA	3		
57	840515 F	THERMOPLASTIC PAVEMENT MARKING	Like 7	SQFT	238		
58	840519 F	THERMOPLASTIC CROSSWALK AND PAVEMENT MARKING	Like 8	SQFT	128		
59	840656 F	PAINT TRAFFIC STRIPE (2-COAT)	Like 9	LF	7,393		
60	015602	FUNDING AWARENESS SIGN	Like 10	EA	1		
61	010602	MISCELLANEOUS WORK (AS DIRECTED)	-----	FA	1	<b>70,000.00</b>	<b>70,000.00</b>

BASE BID SCH. 2

SUB-TOTAL: \_\_\_\_\_ \$ \_\_\_\_\_

ITEMS 44-61 "WORDS"

\* NOTE: See Instructions to Bidders, Section 16 "Like Bid Items", on page A9; corrections will apply if Like Bid items cost discrepancies are submitted. Applicable only to Alternative Bid Schedules 1 and 2. Base Bid Schedule 1 is not included.

**ALTERNATIVE BID SCHEDULE 1 - Frontier Communications (Frontier) Facilities Adjustment**

62	710200	ADJUST MANHOLE	-----	EA	1		
----	--------	----------------	-------	----	---	--	--

ALT. BID SCH. 1

SUB-TOTAL: \_\_\_\_\_ \$ \_\_\_\_\_

ITEM 62 "WORDS"

**ALTERNATIVE BID SCHEDULE 2 - Eastern Municipal Water District (EMWD) Facilities Relocation**

63	202027	RELOCATE WATER METER	-----	EA	2		
----	--------	----------------------	-------	----	---	--	--

ALT. BID SCH. 2

SUB-TOTAL: \_\_\_\_\_ \$ \_\_\_\_\_

ITEM 63 "WORDS"

**BASE BID SCH. 1 + BASE BID SCH. 2 + ALT. BID SCH. 1 + ALT. BID SCH. 2**

**PROJECT TOTAL**

**TOTAL:** \_\_\_\_\_ \$ \_\_\_\_\_

**ITEMS 1-63 "WORDS"**