

**Pourroy Road Widening Project
From Pourroy Road/ Pourroy Road Intersection
To 900-Feet North of This Intersection
Community of French Valley, and
Murrieta Hot Springs Road Sidewalk Project
500-Feet North and South of Chandler Drive
Community of Murrieta Hot Springs
Project No. D3-0094**

PROPOSAL

ITEM No.	ITEM CODE	ITEM	UNIT	ESTIMATED QUANTITY	ITEM PRICE (IN FIGURES)	TOTAL (IN FIGURES)
BASE BID SCHEDULE - Pourroy Road Widening and Murrieta Hot Springs Road Sidewalk Project						
1	066100	DUST ABATEMENT	LS	1		
2	100100	DEVELOP WATER SUPPLY	LS	1		
3	120100	TRAFFIC CONTROL SYSTEM	LS	1		
4	130301	STORMWATER POLLUTION PREVENTION PLAN	LS	1		
5	170103	CLEARING AND GRUBBING	LS	1		
6	190101 F	ROADWAY EXCAVATION	CY	690		
7	192037	STRUCTURE EXCAVATION (RETAINING WALL)	CY	1,260		
8	193013	STRUCTURE BACKFILL (RETAINING WALL)	CY	1,000		
9	193031	PERVIOUS BACKFILL MATERIAL (RETAINING WALL)	CY	65		
10	198010	EMBANKMENT (REBUILD/REGRADE EMBANKMENT)	CY	18		
11	210260	ROLLED EROSION CONTROL PRODUCT (JUTE MESH)	SQFT	1,100		
12	210430	HYDROSEED	SQFT	6,400		
13	260203	CLASS 2 AGGREGATE BASE	CY	480		
14	390132	HOT MIX ASPHALT (TYPE A)	TON	380		
15	394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)	LF	113		
16	510060	STRUCTURAL CONCRETE (RETAINING WALL)	CY	400		
17	520103 F	BAR REINFORCING STEEL (RETAINING WALL)	LB	24,260		
18	710260	REMOVE CONCRETE (CHANNEL)	CY	20		
19	730045	MINOR CONCRETE (CROSS GUTTER)	CY	7		
20	730045	MINOR CONCRETE (WALL GUTTER, DOWN DRAIN, BROW DITCH, V-DITCH)	CY	61		
21	150716	REMOVE PAINTED TRAFFIC STRIPE, PAVEMENT MARKING, AND PAVEMENT MARKERS	LS	1		
22	810130	REMOVE DELINEATOR	EA	31		
23	820280	REMOVE ROADSIDE SIGN (METAL POST)	EA	1		
24	820310	REMOVE ROADSIDE SIGN PANEL	EA	2		
25	820840	ROADSIDE SIGN (ONE POST)	EA	4		

PROPOSAL

ITEM No.	ITEM CODE	ITEM	UNIT	ESTIMATED QUANTITY	ITEM PRICE (IN FIGURES)	TOTAL (IN FIGURES)
BASE BID SCHEDULE - Pourroy Road Widening and Murrieta Hot Springs Road Sidewalk Project (continued)						
26	820900	INSTALL ROADSIDE SIGN PANEL ON EXISTING POST	EA	2		
27	832007	MIDWEST GUARDRAIL SYSTEM (WOOD POST)	LF	360		
28	839584	MIDWEST GUARDRAIL SYSTEM (ALTERNATIVE IN-LINE TERMINAL SYSTEM)	EA	1		
29	839585	MIDWEST GUARDRAIL SYSTEM (ALTERNATIVE FLARED TERMINAL SYSTEM)	EA	1		
30	839521	CABLE RAILING (RETAINING WALL)	LF	484		
31	839643	CONCRETE BARRIER (TYPE 60MD)	LF	484		
32	840516	THERMOPLASTIC PAVEMENT MARKING	SQFT	700		
33	840656	PAINT TRAFFIC STRIPE (2-COAT) [INCLUDES INSTALLATION OF NEW RPMs]	LF	5,600		
34	872133	TRAFFIC SIGNAL MODIFICATON	LS	1		
35	015602	FUNDING AWARENESS SIGN	EA	2		
36	017310	MINOR CONCRETE(RESIDENTIAL DWY APPROACH) CITY OF TEMECULA STD 207 REV	SQFT	250		
37	731502	MINOR CONCRETE (MISCELLANEOUS CONSTRUCTION) [DRIVEWAY 8 INCHES]	SQFT	200		
38	731521	MINOR CONCRETE (SIDEWALK)	SQFT	5,254		
39	800340	CHAIN LINK FENCE (TYPE CL-5)	LF	300		
40	010602	MISCELLANEOUS WORK (AS DIRECTED)	FA	1	50,000.00	50,000.00

PROJECT

TOTAL: _____ \$ _____

ITEMS 1 - 40

"WORDS"