Scheduling Guides

Contents

- Introduction
- Scheduling Documents
 - Schedule Preparation template (MS Excel)
 - Schedule Tracking Summary template (MS Excel)
 - RCTD Program Level Schedule Activities
- Sample Program Level Schedule

Introduction

Project schedules are needed to adequately monitor work progress on projects. Consultants are expected to develop detailed schedules that can be used by the Contract Administrator to track the progress of the Consultant work. Consulting services may, however, only be a part of the of the overall project and represent only a portion of the schedule. RCTD has developed several schedule tracking forms that are intended to facilitate the tracking of the entire project consistent with typical needs for RCTD projects and in a manner that facilitates managing individual projects as part of the overall capital improvement program.

Schedule Preparation Template

This template has been prepared to assist in the initial preparation of a project schedule. The template lists the key scheduling tasks and allows for the quick mockup of a project schedule.

Schedule Tracking Summary

This template is part of the on-going project tracking information that is provided by the Consultant at regular PDT meetings. It provides an overview of the status of certain key milestones and monitors slippage on a monthly basis.

RCTD Program Level Schedule Activities

This template also contains a listing of the standard scheduling tasks but additionally includes the relevant task and status code information.

PROJECT SCHEDULE

PROJECT NAME & LIMITS:

ë

PREPARED BY:

						0000
TASK	Ψ±	START	FINISH	2017 3 A S O N D J F M A M J A S O N D J F M A M J J A S O N D	J F M A M J J A S O N D J	ш
				¥.	018 FY 2019	FY 2020
Inter-Agency Agreements						
Fund Authorization - DES/ENV	RKN					
Procure Consultant - DES/ENV						
Conceptual Design						
Project Study Report						
Right-of-Entry						
Preliminary Survey	EDH					
Preliminary Design						
Project Report						
Environmental Docs						
Environmental Permits						
Final Design (PS&E)						
Fund Authorization - ROW	RKN					
Right-of-Way Engineering	EDH					
Right-of-Way Possession	ЕДН					
Utility Relocations	HLG					
Encroachment Permits						
Fund Authorization - CON	RKN					
Award Process	7					
Procure Consultant - CM	HMS					
Construction	HMS					
Final Seal Coat	HMS					
Landscape Establishment	HMS					
Notice of Completion	HMS					
Final Progress Report	R N					
Project Close-Out						
					- - - - - - -	

PROJECT SCHEDULE SUMMARY

PROJECT:	PROGRESS UPDATE NUMBER:
CONSULTANT:	DATE:

MILESTONES	TARGET	LAST MONTH	THIS MONTH	Si	LIP
MILESTONES	IARGEI	LAST MONTH	THIS MONTH	FROM TARGET	FROM LAST MO
	Date	Date	Date	Days	Days
A&ED					
Complete Environmental Studies					
Approval of Geometry & Bridge Types					
Circulate Draft Environmental Document					
Approval of Final Environmental Document					
PS&E					
Start Final PS&E					
Submit 60% PS&E					
Submit 95% PS&E					
Submit 100% PS&E					
RIGHT-OF-WAY					
Complete Right-of-way Requirements					
Start Appraisals					
Start Offers					
Obtain Certification					
WARD					
Ready to List					
Award					
, wait					
CONSTRUCTION					
Notice to Proceed					
Substantially Complete					

DEADLINE	DUE ON
	Date
DEADLINES	

Group (Rang		Group Category	Code	Description (Less Detailed)	Code	Description (Detailed)	Scheduled Tasks
100-1	149	Removed From TIP	110	Project was Dropped Project was Annexed/Incorporated Project was Conditioned to Developer	100 110 120	Project was Dropped Project was Annexed/Incorporated Project was Conditioned to Developer	Manually Set Removal Status
150-1	189	Inactive	150 160	Project is On Hold Project is On Hold (Pending Funding)	150 160	Project is On Hold Project is On Hold (Pending Funding)	Manually Set Inactive Status
190-1	199	Not Started		Other Pending Project Start	190	Other Pending Project Start	Auto Set if No Progress
200-2	299	Project Initiation	210	Preparing Inter-Agency Agreements	200 210	Pending Inter-Agency Agreements Preparing Inter-Agency Agreements	210 Inter-Agency Agreements
			230	Obtaining Design/Environmental Funding Authorization	220 230	Pending Design/Environmental Funding Authorization Obtaining Design/Environmental Funding Authorization	230 Fund Authorization - DES/ENV
			250	Procuring Design/Environmental Consultant	240 250 260	Pending Design/Environmental Consultant Procurement Procuring Design/Environmental Consultant Pending Conceptual Design Alternatives	250 Procure Consultant - DES/ENV
			270	Preparing Conceptual Design Alternatives	270 280	Preparing Conceptual Design Alternatives Pending Project Study Report	270 Conceptual Design
300-3	399	PA & ED (Project Approval & Environmental		Preparing Project Study Report	300	Preparing Project Study Report Pending Right-of-Entry	290 Project Study Report
		Document)		Obtaining Right-of-Entry Performing Preliminary Surveys	305 310 315	Obtaining Right-of-Entry Pending Preliminary Survey Performing Preliminary Survey	305 Right-of-Entry 315 Preliminary Survey
				Preparing Environmental Documents	320 330	Pending Environmental Documents Preparing Environmental Documents	330 Environmental Docs
			350	Preparing Preliminary Plans	340 350 360	Pending Preliminary Plans Preparing Preliminary Plans Pending Project Report	350 Preliminary Design
			370	Preparing Project Report	370 380	Preparing Project Report Pending Environmental Permits	370 Project Report
400-4	499	Design	390	Processing Environmental Permits	390 400	Processing Environmental Permit Pending Final Plans Specs. & Estimates	390 Environmental Permits
500-5	599	Right-of-Way/Utilities		Preparing Final Plans Specs. & Estimates Obtaining Right-of-Way Funding Authorization	500 510	Preparing Final Plans Specs. & Estimates Pending Right-of-Way Funding Authorization Obtaining Right-of-Way Funding Authorization	410 Final Design (PS&E) 510 Fund Authorization - ROW
			530	Preparing Right-of-Way Engineering Docs.	520 530	Pending Right-of-Way Engineering Docs. Preparing Right-of-Way Engineering Docs.	530 Right-of-Way Engineering
			550	Obtaining Right-of-Way Possession	540 550 560	Pending Right-of-Way Possession Obtaining Right-of-Way Possession Pending Utility Relocations	550 Right-of-Way Possession
600-6	699	Award Processing	570	Relocating Utilities	570 600	Relocating Utilities Pending Encroachment Permits	570 Utility Relocations
				Obtaining Encroachment Permits	610 620	Obtaining Encroachment Permits Pending Construction Funding Authorization	610 Encroachment Permits
				Obtaining Construction Funding Authorization Processing Award	630 640 650	Obtaining Construction Funding Authorization Pending Award Process Processing Award	630 Fund Authorization - CON 650 Award Process
700-7	799	Construction		Procuring Construction Management Consultant	700 710	Pending Construction Management Consultant Procurement Procuring Construction Management Consultant	710 Procure Consultant - CM
			730	Under Construction	720 730 740	Pending Construction Under Construction Pending Final Seal Coat	730 Construction
			750	Placing Final Seal Coat	750 760	Placing Final Seal Coat Pending Landscape Establishment	750 Final Seal Coat
800-8	899	Project Close-Out	770	Monitoring Landscape Establishment	770 800	Monitoring Landscape Establishment Pending Notice of Completion	770 Landscape Establishment
				Processing Notice of Completion Preparing Final Progress Report	810 820 830	Processing Notice of Completion Pending Final Progress Report Preparing Final Progress Report	810 Notice of Completion 830 Final Progress Report
				Processing Project Close-Out	840 850	Pending Close-Out Process Processing Close-Out	850 Project Close-Out
			855 860	Administrative Functions Only Claims Resolution	855 860	Administrative Functions Only Claims Resolution	Manually Set Close-Out Statu
			865 870	Processing Acceptance into Road System Obtain Right-of-Way Ownership	865 870	Processing Acceptance Into Road System Obtain Right-of-way Ownership	
900-9	909	Project Completed	900	Project Completed	900	Project Completed	Auto if all tasks complete or car Manually Set

Printed 1:21 PM, Tuesday, June 21, 2016	H H H H H H H H H H H H H H H H H H H		
	FY 2020	JASONDJFMAMJ	
	FY 2019	JASONDJFMAM	
	FY 2018	1	
	FY 2017	JASONDJFMAMJ	
	FY 2016	O S A U	
	FY 2015	JASONDJFMAMJ	
	ľ	SIAKI FINISH	
		SPEINI SI	
	F	BODGEI	
	OTOLYGIA TGIOTIO	5	
	OF 01335	ASSIGNED TO	
Project Schedules	7.0 × F	IAON	

C5-0072.00 Temescal Canyon Ro	.00 Temescal Canyon Rd: Dawson Canyon Rd to N'ly Dawson Cyn 0.7 mi	"ly Dawson Cyn 0.7 mi			Cathy Wampler <equation-block></equation-block>
Preliminary Survey Ec	Ed Hunt	\$127,000	\$96,688 07/28/15 01/20/16	1/20/16	
Environmental Docs M.	Marcia Rose Dokken Engineering	\$522,000	\$90,288 10/26/15 10/16	10/16/16	
Preliminary Design Ca	Cathy Wampler NCM		01/18/16 05/31/16	9/3/1/6	
Final Design (PS&E)	Cathy Wampler NCM	\$1,501,000	\$159,993 03/28/16 03/03/17	3/03/17	
Right-of-Way Engineering Ec	Ed Hunt		08/01/16 11/30/16	U30/16	
Environmental Permits M.	Marcia Rose Dokken Engineering	Ď.	10/12/16 02/14/17	2/14/17	
Right-of-Way Possession	Ed Hunt EDA Real Estate Division	ivision \$2,453,000	\$2,872 12/16/16 12/08/17	2/08/17	
Award Process Jo	Joel Jimenez		12/11/17 03/11/	03/11/18	
Utility Relocations He	Hermino Garcia	\$55,000	02/01/18 04/30	04/30/18	
Construction	Hugh Smith	000'069'9\$	03/25/18 03/10	03/10/19 Committed to	Commited to Supervisor
Notice of Completion	Hugh Smith		03/11/19 07/11/	07/11/19	





Q - Award MM - Notice of Completion



