

## MINIMUM CEMENTITIOUS MATERIAL CONTENT = 505 LB / CU YD

0.888 CU FT / LF 1 CU YD = 30.41 LF

## NOTES:

- 1. RELATIVE COMPACTION OF SUBGRADE UNDER CURB AND GUTTER AND NEW PAVEMENT SHALL BE 95% MINIMUM.
- 2. WHEN ABUTTING SOIL HAS A HIGH SULFATE CONTENT, USE A MODIFIED CONCRETE MIX AND PLACE 6" MIN CLASS 2 AGGREGATE BASE AND 6 MIL PLASTIC SHEETING UNDER AND AROUND ALL SIDES OF CONCRETE IMPROVEMENTS. FOR EXPANSIVE SOIL, PLACE 6" MIN CLASS 2 AGGREGATE BASE UNDER CONCRETE IMPROVEMENTS AS DIRECTED BY THE ENGINEER. SEE SPECIFICATIONS SECTIONS 16.03 & 16.04 AND STANDARD No. 401 FOR REFERENCE.

NOT TO SCALE PROFESS. PREPARED UNDER THE SUPERVISION OF: REGISTERS -COUNTY OF RIVERSIDE ENGINEER coll 11/30/22 DIRECTOR OF TRANSPORTATION DATE TYPE "D" CURB ONLY MARK LANCASTER, P.E. REVISION DESCRIPTION MARK DATE APPROVED OF CALIFORN STANDARD No. 204