

**Riverside County Transportation Department
Summary of Bids**

**PROJECT: 42nd Street and Tilton Avenue
PROJECT No: B0-0484**

Bids Open: 2:00 p.m. DATE: May 31, 2000

				COUNTY'S ESTIMATE			H & H General Contractors San Bernardino, CA 92427	
ITEM NO.	ITEM CODE	CONTRACT ITEM	UNITS	QUANTITY	UNIT PRICE	ENG ESTIMATE	BID	AMOUNT
1	120100	TRAFFIC CONTROL SYSTEM	LS	1	7,000.00	7,000.00	13,000.00	13,000.00
2	190101	ROADWAY EXCAVATION	CY	349	40.00	13,960.00	26.00	9,074.00
3	017302	MINOR CONCRETE (CROSS-GUTTER) (CRS 209)	SQFT	2,279	5.00	11,395.00	5.00	11,395.00
4	260201	CLASS 2 AGGREGATE BASE	CY	112	30.00	3,360.00	65.00	7,280.00
5	017305	MINOR CONCRETE (CURB AND GUTTER) (CRS 201)	LF	1,188	12.00	14,256.00	12.00	14,256.00
6	390172	ASPHALT CONCRETE (TYPE B)	TON	82	60.00	4,920.00	80.00	6,560.00
7	731521	MINOR CONCRETE (SIDEWALK)	SQFT	7,534	3.00	22,602.00	2.00	15,068.00
8	017310	MINOR CONCRETE (DRIVEWAY APPROACH)(CRS 207)	SQFT	1,310	5.00	6,550.00	5.70	7,467.00
9	017316	MINOR CONCRETE (CURB RAMP) (CRS 403 - CASE B)	EA	6	1,000.00	6,000.00	1,782.00	10,692.00
10	152380	RELOCATE CHAIN LINK FENCE	LF	250	15.00	3,750.00	9.00	2,250.00
11	152370	RELOCATE MAILBOXES	EA	5	100.00	500.00	250.00	1,250.00
12	220101	FINISHING ROADWAY	LS	1	7,000.00	7,000.00	2,500.00	2,500.00
13	860811	DETECTOR LOOP	EA	1	500.00	500.00	500.00	500.00
14	869040	PULL BOX	EA	1	500.00	500.00	1,200.00	1,200.00
TOTALS:							102,293.00	102,492.00

**Riverside County Transportation Department
Summary of Bids**

**PROJECT: 42nd Street and Tilton Avenue
PROJECT No: B0-0484**

Bids Open: 2:00 p.m. DATE: May 31, 2000

					E.G.N. Construction, Inc. Pomona, CA 91766		Hillcrest Contracting, Inc. Corona, CA 91718-1898	
ITEM NO.	ITEM CODE	CONTRACT ITEM	UNITS	QUANTITY	BID	AMOUNT	BID	AMOUNT
1	120100	TRAFFIC CONTROL SYSTEM	LS	1	6,400.00	6,400.00	5,500.00	5,500.00
2	190101	ROADWAY EXCAVATION	CY	349	60.00	20,940.00	56.00	19,544.00
3	017302	MINOR CONCRETE (CROSS-GUTTER) (CRS 209)	SQFT	2,279	3.75	8,546.25	4.80	10,939.20
4	260201	CLASS 2 AGGREGATE BASE	CY	112	64.00	7,168.00	127.00	14,224.00
5	017305	MINOR CONCRETE (CURB AND GUTTER) (CRS 201)	LF	1,188	11.70	13,899.60	13.50	16,038.00
6	390172	ASPHALT CONCRETE (TYPE B)	TON	82	150.00	12,300.00	102.00	8,364.00
7	731521	MINOR CONCRETE (SIDEWALK)	SQFT	7,534	2.50	18,835.00	2.75	20,718.50
8	017310	MINOR CONCRETE (DRIVEWAY APPROACH)(CRS 207)	SQFT	1,310	3.65	4,781.50	3.60	4,716.00
9	017316	MINOR CONCRETE (CURB RAMP) (CRS 403 - CASE B)	EA	6	850.00	5,100.00	500.00	3,000.00
10	152380	RELOCATE CHAIN LINK FENCE	LF	250	15.00	3,750.00	9.00	2,250.00
11	152370	RELOCATE MAILBOXES	EA	5	150.00	750.00	100.00	500.00
12	220101	FINISHING ROADWAY	LS	1	3,900.00	3,900.00	3,000.00	3,000.00
13	860811	DETECTOR LOOP	EA	1	750.00	750.00	500.00	500.00
14	869040	PULL BOX	EA	1	750.00	750.00	500.00	500.00
TOTALS:						107,870.35		109,793.70

**Riverside County Transportation Department
Summary of Bids**

**PROJECT: 42nd Street and Tilton Avenue
PROJECT No: B0-0484**

Bids Open: 2:00 p.m. DATE: May 31, 2000

			Sean Malek Eng. & Const. Perris, CA 92571			
ITEM NO.	ITEM CODE	CONTRACT ITEM	UNITS	QUANTITY	BID	AMOUNT
1	120100	TRAFFIC CONTROL SYSTEM	LS	1	15,000.00	15,000.00
2	190101	ROADWAY EXCAVATION	CY	349	50.00	17,450.00
3	017302	MINOR CONCRETE (CROSS-GUTTER) (CRS 209)	SQFT	2,279	6.00	13,674.00
4	260201	CLASS 2 AGGREGATE BASE	CY	112	60.00	6,720.00
5	017305	MINOR CONCRETE (CURB AND GUTTER) (CRS 201)	LF	1,188	16.00	19,008.00
6	390172	ASPHALT CONCRETE (TYPE B)	TON	82	125.00	10,250.00
7	731521	MINOR CONCRETE (SIDEWALK)	SQFT	7,534	2.50	18,835.00
8	017310	MINOR CONCRETE (DRIVEWAY APPROACH)(CRS 207)	SQFT	1,310	4.00	5,240.00
9	017316	MINOR CONCRETE (CURB RAMP) (CRS 403 - CASE B)	EA	6	850.00	5,100.00
10	152380	RELOCATE CHAIN LINK FENCE	LF	250	25.00	6,250.00
11	152370	RELOCATE MAILBOXES	EA	5	50.00	250.00
12	220101	FINISHING ROADWAY	LS	1	10,000.00	10,000.00
13	860811	DETECTOR LOOP	EA	1	650.00	650.00
14	869040	PULL BOX	EA	1	500.00	500.00
TOTALS:						128,927.00

